

D. RATES OF CARBON FORMATION EXPERIMENTAL PROGRAM

1. Description of Experimental Equipment

During the period July - September, 1977, the design of the multiple fixed-bed reactor system was completed (see Figure IV-D-1 and IV-D-2). Equipment was ordered and a fabricator was commissioned to construct the reactor unit. The reactor design incorporates a removable, sectional catalyst basket which can be positioned inside the reactor tube. The baskets contain provisions for a central thermowell. The thermowell contains three stationary thermocouples for zone temperature controllers in addition to the traveling thermocouple necessary for the temperature profile.


Construction of the test unit assembly (support structure and piping) started in October, 1977. The overall dimensions are 19 ft. long, 4 ft. wide, and 7 ft. high. It is subdivided into five identical units, one for each reactor system, and a master control panel to hold the temperature indicator and recorder.

The feed gas lines from the trailer to the reactor skid were completed in October. Construction began on a single prototype unit of the reactor system to study the feasibility of several instrument and piping arrangements. The remaining four units were later duplicated from this one.

During November, 1977, the reactor skid housing five individual reactor units was completed. Construction of a modular unit for two gas booster compressors, as shown in Figure IV-D-3, was also finished except for electrical wiring. Construction of a prototype of a single reactor system neared completion. The layout of the control panel of the prototype is shown in Figure IV-D-4.

230
 FIGURE IV-D-1

**SCHEMATIC DIAGRAM OF REACTOR ASSEMBLY
 CARBON FORMATION STUDY IN METHANATION**






FIGURE IV-D-2

CHAM SYSTEMS INC.
1417 F STREET, N.W.
WASHINGTON, D.C. 20004
RATES OF CARBON
FORMATION TEST UNIT
NO. 684

231

CARBON FORMATION BOOSTER
CONTROL PANEL





FIGURE IV-D-4

CARBON FORMATION REACTOR SYSTEM CONTROL PANEL



By the end of November, 1977, all of the long-lead delivery items were received except the high pressure rotameters and drain tanks. High pressure metering pumps had been calibrated at both 500 and 1000 psi operating conditions. The gas chromatograph recorder was found defective and returned for repair.

The high pressure rotameters were received and installed in December, 1977. Electrical wiring of heater, temperature indicator, thermocouple assembly, controller and recorder was also completed. The four duplications of the prototype single reactor unit were also completed in December.

The construction of the analytical unit adjacent to the reactor skid started in December, 1977. The vent and drain lines were installed. The thermocouple wells were fabricated with the attachment to hold the catalyst basket in the reactor.

During January, 1978, the high-pressure drain tanks were received and installed. Electrical wiring of five reactor units on the skid were completed, and construction of the analytical system was nearly finished.

By early February, 1978, both electrical and analytical systems were complete. Each component was then carefully checked for leaks and malfunctions, prior to any experimental work.